FM 4-20.137 (FM 10-537)
AIR FORCE TO 13C7-1-19

AIRDROP OF SUPPLIES AND EQUIPMENT:

# RIGGING FORWARD AREA REFUELING EQUIPMENT (FARE) AND ADVANCED AVIATION FORWARD AREA REFUELING SYSTEM (AAFARS)

**DISTRIBUTION RESTRICTION:** Approved for public release; distribution is unlimited.

**HEADQUARTERS**
**DEPARTMENT OF THE ARMY**
**DEPARTMENT OF THE AIR FORCE**

FIELD MANUAL
NO. 4-20.137
TECHNICAL ORDER
NO. 13C7-1-19

HEADQUARTERS
DEPARTMENT OF THE ARMY
DEPARTMENT OF THE AIRFORCE
WASHINGTON, DC, 10 JUNE 2003

# Airdrop of Supplies and Equipment: Rigging Forward Area Refueling Equipment (FARE) and Advanced Aviation Forward Area Refueling System (AAFARS)

## Contents

Page

**Preface** ..... **viii**

**Introduction** ..... **ix**

**Chapter 1** **Rigging FARE for Low Velocity Airdrop On Type V Platform**

Section I Rigging FARE with Two 500-Gallon Fuel Drums

Description of Load ..... **1-1**
Preparing Platform ..... **1-1**
Preparing Honeycomb ..... **1-3**
Building Container for FARE ..... **1-4**
Preparing and Stowing FARE in Container ..... **1-8**
Securing Container ..... **1-14**
Positioning and Lashing Container ..... **1-16**
Attaching Lifting Slings ..... **1-20**
Placing and Lashing Fuel Drums ..... **1-21**
Installing Suspension Slings ..... **1-25**
Stowing Cargo Parachutes ..... **1-26**
Installing Extraction System ..... **1-27**

**Distribution Restrictions:** Approved for public release; distribution is unlimited.

*This publication supercedes FM 10-537/TO 13C7-1-19, dated 30 September 1999

Page

Installing Parachute Release System ..... 1-29
Placing Extraction Parachute ..... 1-30
Installing Provisions for Emergency Restraints ..... 1-30
Marking Rigged Load ..... 1-30
Equipment Required ..... 1-30

Section II Rigging FARE in an M101 Series, 3/4-Ton Trailer

Description of Load ..... 1-34
Preparing Platform ..... 1-34
Building and Placing Honeycomb Stacks ..... 1-35
Preparing Trailer ..... 1-41
Positioning Trailer ..... 1-51
Lashing Trailer ..... 1-53
Installing Suspension Slings ..... 1-54
Building and Installing Cargo Parachute Stowage Platform ..... 1-55
Stowing Cargo Parachutes ..... 1-57
Installing Extraction System ..... 1-58
Installing Parachute Release System ..... 1-60
Placing Extraction Parachute ..... 1-61
Installing Provisions for Emergency Restraints ..... 1-61
Marking Rigged Load ..... 1-61
Equipment Required ..... 1-61

Section III Rigging FARE in an M998, 1/4-Ton Truck (HMMWV)

Description of Load ..... 1-65
Preparing Platform and Truck ..... 1-65
Preparing Cargo Bed ..... 1-65
Placing FARE In Cargo Bed ..... 1-67
Securing FARE ..... 1-70
Securing Accessories ..... 1-72

Section IV Rigging FARE With Seven 500-Gallon Fuel Drums on a 32-Foot Platform

Description of Load ..... 1-74
Preparing Platform ..... 1-74
Building and Positioning Honeycomb ..... 1-76
Positioning and Lashing Drums ..... 1-78
Preparing FARE ..... 1-87
Installing Lifting Slings and Positioning FARE Containers ..... 1-88
Lashing FARE Containers to Platform ..... 1-88
Installing Suspension Slings ..... 1-93
Safety Tieing Suspension Slings ..... 1-94
Building and Installing Cargo Parachute Stowage Tray ..... 1-95
Preparing and Stowing Cargo Parachutes ..... 1-97
Installing the Extraction System ..... 1-98
Installing Parachute Release System ..... 1-99
Placing Extraction Parachute ..... 1-100
Installing Provisions for Emergency Restraints ..... 1-100

Page

Marking Rigged Load ..... 1-100
Equipment Required ..... 1-100

**Chapter 2 Rigging the 350-GPM Wheel-Mounted POL Pumping Assembly with Filter/ Separator**

Description of Load ..... 2-1
Preparing Platform ..... 2-1
Preparing Honeycomb ..... 2-3
Positioning Honeycomb Stacks ..... 2-7
Preparing the Pump Assembly and Filter/Separator ..... 2-8
Positioning the Pump Assembly and Filter/Separator ..... 2-12
Lashing the Pump Assembly and Filter/Separator to the Platform ..... 2-15
Constructing the Parachute Stowage Tray and Load Cover ..... 2-17
Installing the Suspension Slings and Deadman's Tie ..... 2-19
Preparing, Stowing, and Restraining Cargo Parachutes ..... 2-20
Installing the Extraction System ..... 2-21
Installing Parachute Release System ..... 2-23
Placing Extraction Parachute ..... 2-24
Installing Provisions for Emergency Restraints ..... 2-24
Marking Rigged Load ..... 2-24
Equipment Required ..... 2-24

**Chapter 3 Rigging 500-Gallon Drums with the 350-GPM Wheel-Mounted POL Pumping Assembly, Filter/ Separator Assembly, and Hose Box**

Section I Rigging Three 500-Gallon Drums

Description of Load ..... 3-1
Preparing Platform ..... 3-1
Preparing Honeycomb ..... 3-3
Positioning Honeycomb Stacks ..... 3-11
Building the Equipment Hose Box ..... 3-12
Positioning Equipment Hose Box ..... 3-13
Storing Equipment in Equipment Hose Box ..... 3-14
Lashing Equipment Hose Box To Platform ..... 3-15
Preparing and Positioning Fuel Separator ..... 3-17
Lashing Separator to Platform ..... 3-18
Positioning and Lashing the Drums ..... 3-19
Preparing and Positioning the Pump ..... 3-23
Lashing Pump to the Platform ..... 3-24
Covering the Pump ..... 3-25
Installing Suspension Slings and Safety Ties ..... 3-26
Building and Positioning Parachute Stowage Platform ..... 3-27
Preparing and Stowing Cargo Parachutes ..... 3-28
Installing the Extraction System ..... 3-29
Installing the Cargo Parachute Release System ..... 3-30
Placing Extraction Parachute ..... 3-31
Installing Provisions for Emergency Restraints ..... 3-31
Marking Rigged Load ..... 3-31

Page

Equipment Required ..... 3-31

Section II Rigging Four 500-Gallon Drums

Description of Load ..... 3-35
Preparing Platform ..... 3-35
Preparing Honeycomb ..... 3-37
Positioning Honeycomb Stacks ..... 3-39
Building Equipment Hose Box ..... 3-40
Positioning Equipment Hose Box ..... 3-40
Storing Equipment in the Equipment Hose Box ..... 3-40
Lashing Equipment Hose Box to Platform ..... 3-40
Preparing and Positioning Fuel Separator ..... 3-42
Lashing Fuel Separator to Platform ..... 3-42
Positioning and Lashing Drums ..... 3-43
Preparing and Positioning the Pump ..... 3-49
Lashing the Pump to the Platform ..... 3-49
Covering the Pump ..... 3-50
Installing Suspension Slings and Safety Ties ..... 3-50
Building and Positioning Parachute Stowage Platform ..... 3-51
Preparing and Stowing Cargo Parachutes ..... 3-52
Installing the Extraction System ..... 3-53
Installing the Parachute Release System ..... 3-54
Placing Extraction Parachute ..... 3-55
Installing Provisions For Emergency Restraints ..... 3-55
Marking Rigged Load ..... 3-55
Equipment Required ..... 3-55

Section III Rigging Five 500-Gallon Drums

Description of Load ..... 3-59
Preparing Platform ..... 3-59
Preparing Honeycomb ..... 3-61
Positioning Honeycomb Stacks ..... 3-62
Building Equipment Hose Box ..... 3-63
Positioning Equipment Hose Box ..... 3-63
Storing Equipment in the Equipment Hose Box ..... 3-63
Lashing Equipment Hose Box to Platform ..... 3-63
Preparing and Positioning Fuel Separator ..... 3-65
Lashing Fuel Separator to Platform ..... 3-65
Positioning and Lashing the Drums ..... 3-66
Preparing and Positioning Pump ..... 3-73
Lashing the Pump to the Platform ..... 3-73
Installing Suspension Slings and Safety Ties ..... 3-74
Covering the Pump ..... 3-75
Building and Positioning Parachute Stowage Platform ..... 3-76
Preparing and Stowing Cargo Parachutes ..... 3-77
Installing the Extraction System ..... 3-78
Installing the Parachute Release System ..... 3-79
Placing Extraction Parachute ..... 3-80

Page

Installing Provisions for Emergency Restraints ..... 3-80
Marking Rigged Load ..... 3-80
Equipment Required ..... 3-80

Section IV Rigging Six 500-Gallon Drums

Description of Load ..... 3-85
Preparing Platform ..... 3-85
Preparing Honeycomb ..... 3-87
Positioning Honeycomb Stacks ..... 3-88
Building Equipment Hose Box ..... 3-89
Positioning Equipment Hose Box ..... 3-89
Storing Equipment in the Equipment Hose Box ..... 3-89
Lashing Equipment Hose Box to Platform ..... 3-89
Positioning and Securing Parachute Stack ..... 3-91
Positioning and Lashing the Drums ..... 3-92
Preparing and Positioning the Pump ..... 3-103
Lashing Pump to Platform ..... 3-105
Building, Positioning, and Lashing the Separator Box to the Platform ..... 3-106
Constructing and Positioning the Release Platform ..... 3-112
Installing Suspension Slings and Safety Ties ..... 3-113
Building and Positioning Parachute Stowage Platform ..... 3-115
Preparing and Stowing Cargo Parachutes ..... 3-116
Installing the Extraction System ..... 3-117
Installing the Parachute Release System ..... 3-118
Placing Extraction Parachute ..... 3-119
Installing Provisions for Emergency Restraints ..... 3-119
Marking Rigged Load ..... 3-119
Equipment Required ..... 3-119

**Chapter 4 Rigging AAFARS For Low Velocity Airdrop On Type V Platform**

Section I Rigging AAFARS withThree 500-Gallon Drums Fuel Drums

Description of Load ..... 4-1
Preparing Platform ..... 4-1
Preparing Honeycomb ..... 4-3
Positioning Honeycomb Stacks ..... 4-4
Building the Equipment Boxes ..... 4-5
Preparing Equipment for Equipment Boxes ..... 4-7
Positioning Equipment Boxes ..... 4-19
Positioning and Securing Equipment in Equipment Boxes ..... 4-20
Lashing the Equipment Boxes to the Platform ..... 4-25
Positioning and Lashing the Drums ..... 4-31
Building and Positioning Release Platform ..... 4-39
Installing Suspension Slings and Safety Ties ..... 4-40
Preparing and Stowing Cargo Parachutes ..... 4-41
Installing the Extraction System ..... 4-42
Installing the Cargo Parachute Release System ..... 4-43
Placing Extraction Parachute ..... 4-44

Page

Installing Provisions for Emergency Restraints ..... 4-44
Marking Rigged Load ..... 4-44
Equipment Required ..... 4-44

Section II Rigging AAFARS with Four 500-Gallon Fuel Drums

Description of Load ..... 4-48
Preparing Platform ..... 4-48
Preparing and Positioning Honeycomb Stacks ..... 4-50
Building the Equipment Boxes ..... 4-50
Preparing Equipment for Equipment Boxes ..... 4-50
Positioning Equipment Boxes ..... 4-50
Positioning Equipment in Equipment Boxes and Securing Boxes ..... 4-50
Lashing the Equipment Boxes to the Platform ..... 4-50
Positioning and Lashing Drums ..... 4-57
Installing Release Platform, Suspension Slings and Safety Ties ..... 4-64
Preparing and Stowing Cargo Parachutes ..... 4-66
Installing the Cargo Parachute Release System ..... 4-67
Installing the Extraction System ..... 4-68
Placing Extraction Parachute ..... 4-69
Installing Provisions for Emergency Restraints ..... 4-69
Marking Rigged Load ..... 4-69
Equipment Required ..... 4-69

Section III Rigging AAFARS with Five 500-Gallon Fuel Drums

Description of Load ..... 4-73
Preparing Platform ..... 4-73
Preparing Honeycomb ..... 4-75
Positioning Honeycomb Stacks ..... 4-76
Building the Equipment Boxes ..... 4-77
Preparing Equipment for Equipment Boxes ..... 4-77
Positioning Equipment Boxes ..... 4-77
Positioning Equipment in Equipment Boxes and Securing Boxes ..... 4-77
Lashing the Equipment Boxes to the Platform ..... 4-78
Positioning and Lashing the Drums ..... 4-84
Building and Positioning Release Platform ..... 4-92
Installing Suspension Slings and Safety Ties ..... 4-93
Preparing and Stowing Cargo Parachutes ..... 4-94
Installing the Extraction System ..... 4-95
Installing the Cargo Parachute Release System ..... 4-96
Placing Extraction Parachutes ..... 4-97
Installing Provisions for Emergency Restraints ..... 4-97
Marking Rigged Load ..... 4-97
Equipment Required ..... 4-97

Page

Section IV Rigging AAFARS with Six 500-Gallon Fuel Drums

Description of Load ..... 4-101
Preparing Platform ..... 4-101
Preparing Honeycomb ..... 4-103
Positioning Honeycomb Stacks ..... 4-104
Positioning and Lashing the Drums ..... 4-105
Building the Equipment Boxes ..... 4-116
Preparing Equipment for Equipment Boxes ..... 4-119
Positioning Equipment Boxes ..... 4-122
Positioning and Securing Equipment in Equipment Boxes ..... 4-124
Lashing the Equipment Boxes to the Platform ..... 4-130
Building and Positioning Release Platform ..... 4-136
Installing Suspension Slings and Safety Ties ..... 4-137
Securing the Suspension Slings ..... 4-138
Preparing and Stowing Cargo Parachutes ..... 4-141
Installing the Extraction System ..... 4-142
Installing the Cargo Parachute Release System ..... 4-143
Placing Extraction Parachutes ..... 4-144
Installing Provisions for Emergency Restraints ..... 4-144
Marking Rigged Load ..... 4-144
Equipment Required ..... 4-144

Section V Rigging AAFARS with Seven 500-Gallon Fuel Drums

Description of Load ..... 4-149
Preparing Platform ..... 4-149
Preparing Honeycomb ..... 4-151
Positioning Honeycomb Stacks ..... 4-152
Positioning and Lashing the Drums ..... 4-153
Building the Equipment Boxes ..... 4-166
Preparing Equipment for Equipment Boxes ..... 4-166
Positioning Equipment Boxes ..... 4-166
Positioning and Securing Equipment in Equipment Boxes ..... 4-166
Lashing the Equipment Boxes to the Platform ..... 4-166
Installing Suspension Slings and Safety Ties ..... 4-170
Securing the Suspension Slings ..... 4-170
Preparing and Stowing Cargo Parachutes ..... 4-172
Building and Positioning Release Platform ..... 4-173
Installing the Extraction System ..... 4-174
Installing the Cargo Parachute Release System ..... 4-175
Placing Extraction Parachutes ..... 4-176
Installing Provisions for Emergency Restraints ..... 4-176
Marking Rigged Load ..... 4-176
Equipment Required ..... 4-176

**Appendix A ..... Appendix A-1**
**Glossary ..... Glossary-1**
**References ..... References-1**